

PURCHASE OF PORTABLE HORSE STALLS

IFB #0230

Addendum 3 Amendment Issued February 5, 2020

Page 5, Section 2.2 of the IFB, shall be amended as follows:

2.2 PORTABLE HORSE STALL SPECIFICATIONS

The selected contractor shall provide the materials needed to assemble portable horse stalls at the New York State Fairgrounds. Exhibit 1 shows the layout of the stalls.

A. General Requirements:

- No tools should be required for the assembly of the stalls.
- Contractor shall provide all starter posts necessary to fully assemble the portable horse stalls.
- Assembled horse stalls shall measure 9 feet long and 7 feet high with a 2.75" fork well on top of the frame to act as a secure point for transporting the stall with a forklift.
- Delivery: The price shall include guaranteed delivery to the New York State Fairgrounds no later than ~~April 1, 2020~~ July 1, 2020. AGM will provide a forklift and operator for unloading the portable horse stalls onsite.
- Product Warranty: Contractor must warrant and represent that Products, components or parts specified and furnished by or through Contractor, whether specified and furnished individually or as a system, shall be substantially free from defects in material and workmanship and will conform to all requirements of this solicitation for the manufacturer's standard commercial warranty period, if applicable, or for a minimum of one year from the date of acceptance, whichever is longer (the "Product warranty period").

B. Item 1: Front Panel Specifications

- **Quantity:** 172
- **Panel Dimensions:** 9' L x 7' H
- **Material and Construction:**
 - 14-gauge galvanized frame
 - architectural grade powder coat finish in black
 - door opening of 48" with a swing door that is welded to the stall frame
 - 4 of the doors shall be left hand doors and 168 shall be right hand doors
 - a latch on the door shall allow the use of a padlock
 - the bars on the top 32 inches of the horse stall panel shall be vertical and set 2.25" apart; the diameter of the vertical bars shall be 1.5"
 - the bottom 52 inches of the horse stall panel shall be manufactured from 1/4" HDPE

C. Item 2: Back Panel Specifications

- **Quantity:** 86
- **Panel Dimensions:** 9' L x 7' H
- **Material and Construction:**
 - 14-gauge galvanized frame
 - architectural grade powder coat finish in black
 - the bars on the top 32 inches of the horse stall panel shall be vertical and set 2.25" apart; the diameter of the vertical bars shall be 1.5"
 - the bottom 52 inches of the horse stall panel shall be manufactured from 1/4" HDPE.

D. Item 3: Side Panel Specifications

- **Quantity:** 218
- **Panel Dimensions:** 9' L x 7' H
- **Material and Construction:**
 - 14-gauge galvanized frame
 - architectural grade powder coat finish in black
 - the bars on the top 32 inches of the horse stall panel shall be vertical and set 2.25" apart; the diameter of the vertical bars shall be 1.5"
 - the bottom 52 inches of the horse stall panel shall be manufactured from 1/4" HDPE